## **Amendments to the Vapor Recovery Equipment Defects List**

Note: The propose	d amendments are	e shown in <u>unde</u> ı	rline to indicate	additions and	l strikethrougl	h to
indicate deletions.	All other portions	remain unchang	ed and are indi	cated by the s	symbol "* * * *	*"

# California Environmental Protection Agency

# Air Resources Board

**Vapor Recovery Equipment Defects List** 

Adopted: September 23, 2002 Amended: June 22, 2005 Amended: June 17, 2008 Amended: June 11, 2012

## Vapor Recovery Equipment Defects List

Date of Issuance: June 17, 2008 June 11, 2012

GVR All Sy	GVR All Systems/any E.O.				
equipment	defects verification procedure				
(a) system	(1) any equipment defect which is identified in an Executive Order (EO) certifying a system pursuant to the Certification Procedures incorporated in Section 94011 of Title 17, California Code of Regulations	as set forth in the applicable EO			
	(2) absence, improper installation, or disconnection of any component required to be used in the EO(s) that certified the system	direct observation			
	(3) installation or use of any uncertified component				
	(4) dispensing rate greater than ten (10.0) gallons per minute (gpm) or less than the greater of five (5.0) gpm or the limit stated in the EO measured at maximum fuel dispensing	when determined as part of any ARB approved test method or direct measurement for 30 seconds minimum			
	(5) Phase I vapor poppet inoperative	direct observation			
(b) nozzles	(1) nozzle automatic liquid shutoff mechanisms which malfunction in any manner	EPO No. 26-F-1/direct observation			

Note: Each defect in the tables in this list has a specific alphanumeric identification. Every identification has three parts: i)

- i) the Executive Order (E.O.) number for the table in which the defect appears (or GVR-(general vapor recovery-) for this "GVR All Systems/any E.O." page table only), ii)
- ii) a sequential letter for the equipment with which the defect is associated, and iii). As the "equipment " column in the table changes the equipment number sequence that is associated with the specific equipment begins again with the letter "(a)".
- a sequential number for the defect itself. As the "equipment" column in the table changes, the defect number sequence that is associated with the specific equipment begins again with the number one ("(1)"). The same is true for the equipment letter: at the start of a new table, the first identifying letter associated with the first equipment listed will be "a," the second "b," and so on. The Executive Order number (part i) is comprised of the characters which proceed the literal description of the system.

For example, the identification for the defect above which is written "installation or use of any uncertified component" is "GVR (a) (3)". and the last defect on the next table (page 2) is "G-70-7(d) (1)."

See page 16 for additional examples of each of these changes.

\* \* \* \*

VR-201 series Healy Phase II EVR System not including ISD				
equipment	defects verification procedure			
(a) nozzles (1) defective vapor valve		TP-201.2B - Flow and Pressure  Measurement of Vapor  Recovery Equipment or equivalent, or VR-201 Exhibit 7  - Nozzle Bag Test Procedure		
	(2) any fueling point whose V/L ratio is determined to be at or below 0.80	VR-201 Exhibit 5 <u>Vapor to</u> <u>Liquid Volume Ratio for Healy</u> <u>Phase II EVR System</u>		
(b) <del>system</del> vapor pump	(1) inoperative vapor pumps *	direct observation in accordance with the Healy IOMM, Scheduled Maintenance, section 1.1 paragraph 3 et <u>sSeq</u> .		
(c) clean air separator (CAS)	(1) clean air separator static pressure performance failure *	VR-201 Exhibit 4 <u>—</u> Determination of Static Pressure Performance of the Healy Clean Air Separator		
	(2) clean air separator not in the proper operating configuration *	direct observation shown in VR-201 Exhibit 2		
	(2) ball valves are not in the proper operating configuration as shown in Figures in Exhibit 2 *	direct observation/ shown in VR-201 Exhibit 2 – System Specifications		
(d) dispenser	(1) any dispenser with a dispenser piping test valve in the closed position	direct observation		

<sup>\*</sup> When the identified defect is detected in the listed equipment, the defect determination applies to all affected interrelated systems (which may include all systems at the motor vehicle fueling operation).

VR-202 series Healy Phase II EVR System Including ISD				
equipment	defects	verification procedure		
(a) nozzles	(1) defective vapor valve	TP-201.2B - Flow and Pressure Measurement of Vapor Recovery Equipment or equivalent, or VR-202 Exhibit 7 - Nozzle Bag Test Procedure		
	(2) any fueling point whose V/L ratio is determined to be at or below 0.80	VR-202 Exhibit 5 <u></u> Vapor to Liquid Volume Ratio for Healy Phase II EVR System		
(b) system vapor pump	(1) inoperative vapor pumps *	direct observation in accordance with the Healy IOMM, Scheduled Maintenance, section 1.1 paragraph 3 et sSeq.		
(c) clean air separator (CAS)	(1) clean air separator static pressure performance failure *	VR-202 Exhibit 4 <u>—</u> Determination of Static Pressure Performance of the Healy Clean Air Separator		
	(2) clean air separator not in the proper operating configuration *	direct observation/ shown in VR-202 Exhibit 2		
	(2) ball valves are not in the proper operating configuration as shown in Figures in Exhibit 2 *	direct observation/ shown in VR-202 Exhibit 2 – System Specifications		
(d) dispenser	(1) any dispenser with a dispenser piping test valve in the closed position	direct observation		

<sup>\*</sup> When the identified defect is detected in the listed equipment, the defect determination applies to all affected interrelated systems (which may include all systems at the motor vehicle fueling operation).

equipment	defects	verification procedure
(a) <u>VST</u> (1) more than 30 percent (30%) of a nozzle face seal is missing (e.g triangular or similar shape in which greater than two and one half (2 inches of the face seal circumference is missing (accumulated))		direct measurement/ observation
	(2) more than 0.4375 square inches of a nozzle vapor collection sleeve is missing (e.g., a rectangular shape of greater than nine sixteenths (9/16) inch or more on each side, a circular shape of eleven sixteenths (11/16) inch or more in diameter, or a triangular shape of seven eighths (7/8) inch on the side	direct measurement/ observation
	(3) total cumulative slit length in the convolution/s exceeds 18.0 inches	direct measurement/ observation
	(4) insertion interlock mechanism which will allow dispensing when the convolution is uncompressed	direct observation/GDF-09
(b) EMCO nozzle	(1) more than 0.4 square inches of a nozzle boot face material is missing (e.g., a triangular or similar shape in which greater than 7/16 inches of the boot face circumference is missing (accumulated))	direct measurement/ observation
	(2) slit across seven (7) consecutive bellows convolutions	direct measurement/ observation
	(3) a 360 degree cut around the bellows convolutions	direct measurement/ observation
(c) all nozzles	(51) defective vapor valve	VR-203 <del>Exhibit 10</del> <u>Exhibit 7 –</u> <u>Nozzle Bag Test Procedure</u>
	(62) vapor valve leak rate exceeds 0.07 cubic feet per minute at a pressure of two (2) water column inches	TP-201.2B <u>- Flow and</u> Pressure Measurement of <u>Vapor Recovery Equipment</u>
	(3) nozzle lever has spring tension (live lever) when the vapor recovery sleeve or bellows/convolutions is uncompressed	direct observation
(b <u>d</u> ) hoses	(1) <del>175</del> 150 ml or more liquid in the vapor path	direct measurement/ sections 6.1 to 6.5 of VR-203 Exhibit 5 - Liquid Removal Test Procedure
	(2) any hose with a visible opening	direct observation
(ee) <u>VST</u>	(1) unit inoperative *	direct observation
ECS process <u>or</u> ing unit	$(\underline{12})$ ball valves are not locked in the proper operating configuration as shown in Figures in Exhibit 2 * $\underline{2B-2}$	direct observation/ shown in VR-203 Exhibit 2- System Specifications
	(23) unit is not on or not in the automatic vapor processor mode*	diagnostic section within the VST ECS Membrane Processor: Veeder-Root Pressure Management Control (section 12 of IOMM) of the Pressure Measurement Control (section 16) of IOM

<sup>\*</sup> When the identified defect is detected in the listed equipment, the defect determination applies to all affected interrelated systems (which may include all systems at the motor vehicle fueling operation)

VD 202 paries VCT Dhaga II EVD System canonat including ICD					
VIX-203 Selles V	VR-203 series VST Phase II EVR System sans not including ISD				
<u>equipment</u>	defect	verification procedure			
	(4) processor alarms for emission factor are activated for two consecutive 24 hour periods	direct observation			
	(5) unit fails to activate when the UST pressure is less than or equal to 0.4 water column inch	<del>VR-203 Exhibit 9</del>			
	-(6) hydrocarbon concentration exceeds 12 percent (12%)	vapor processor status report			
(f) vapor polisher	(1) ball valves are not in the proper operating configuration as shown in Figure in Exhibit 2 (except when maintenance or testing is being conducted.) *	direct observation / shown in Figures in VR-203 Exhibit 2 – System Specifications			
	(2) unit is not on or in the automatic vapor processor mode (except when maintenance or testing is being conducted.) *	PMC Diagnostic report per 'PMC Diagnostic Menus' section within the Veeder-Root Vapor Polisher: Pressure Management Control (section 15 of IOMM)			
(g) thermal oxidizer	(12) ball valves are not in the proper operating configuration as shown in Figure in Exhibit 2 *	direct observation / shown in Figures in VR-203 Exhibit 2 – System Specifications			
	(23) thermal oxidizer indicator panel "power on" lamp off *	direct observation			
(h) clean air separator (CAS)	(1) ball valves are not in the proper operating configuration as shown in Figures in Exhibit 2 * (except when maintenance or testing is being conducted.)	direct observation/ shown in VR-203 Exhibit 2 – System Specifications			
	(2) clean air separator static pressure performance failure *	VR-203 Exhibit 14 -Determination of Static Pressure Performance of the Healy Clean Air Separator			
(d) vapor return lines	(1) pressure drop through the vapor path exceeds five (5.00) water column inches at a flow rate of 60 cubic foot per hour (CFH) and eight (8.00) water column inches at a flow rate of 80 CFH	TP201.4 Methodology 1 or equivalent			

<sup>\*</sup> When the identified defect is detected in the listed equipment, the defect determination applies to all affected interrelated systems (which may include all systems at the motor vehicle fueling operation).

### Example of specific three part alphanumeric identification:

Part i example: The EO number is comprised of the characters that precede the literal description of the system (VR-203 series VST Phase II EVR System sans not including ISD.

Part ii example: A second model of nozzle has been added to that EO therefore nozzles are now lettered as a, b and c (VST, EMCO, and all nozzles).

Part iii example: In VR-203 the verification procedure for the defect 'unit is inoperative' is different for all three processors listed in this EO. You will note that the VR-203 table has changes related to this as VR-203 (e) (1) through VR-203 (g) (1) VR-204 series VST Phase II EVR System Including ISD.

VR-204 series VST Phase II EVR System Including ISD				
<u>equipment</u>	defect	verification procedure		
(a) VST nozzle	(1) more than 30 percent (30%) of a nozzle face seal is missing (e.g., a triangular or similar shape in which greater than two and one half (2.5) inches of the face seal circumference is missing (accumulated))	direct measurement/ observation		
	(2) more than 0.4 square inches of a nozzle vapor collection sleeve is missing (e.g., a rectangular shape of greater than nine sixteenths (9/16) inch or more on each side, a circular shape of eleven sixteenths (11/16) inch or more in diameter, or a triangular shape of seven eighths (7/8) inch on the side	direct measurement/ observation		
	(3) cumulative slit length in the convolution/s exceeds 18.0 inches	direct measurement/ observation		
(b) EMCO nozzle	(1) more than 0.4 square inches of a nozzle boot face material is missing (e.g., a triangular or similar shape in which greater than 7/16 inches of the boot face circumference is missing (accumulated))	direct measurement/ observation		
	(2) slit across seven (7) consecutive bellows convolutions	direct measurement/ observation		
	(3) there is a 360 degree cut around the bellows convolutions	direct measurement/ observation		
(c) all nozzles	(1) defective vapor valve	VR-204 Exhibit 7 – Nozzle Bag Test Procedure		
	(2) vapor valve leak rate exceeds 0.07 cubic feet per minute at a pressure of two (2) water column inches	TP-201.2B - Flow and Pressure  Measurement of Vapor Recovery  Equipment		
	(3) nozzle lever has spring tension (live lever) when the vapor recovery sleeve or bellows/convolutions is uncompressed	direct observation		
(d) hoses	(1) 150 ml or more liquid in the vapor path	direct measurement/ sections 6.1 to 6.5 of VR-204 Exhibit 5 - Liquid Removal Test Procedure		
	(2) any hose with a visible opening	direct observation		
(e) VST ECS processor	(1) ball valves are not in the proper operating configuration as shown in Figures in Exhibit 2 *	direct observation/ shown in VR-204 Exhibit 2 – System Specifications		
	(2) unit is not on or in the automatic vapor processor mode *	diagnostic section within the Veeder-Root ISD Manual (section 12 of IOMM)		
(f) vapor polisher	(1) ball valves are not in the proper operating configuration as shown in Figures in Exhibit 2 * (except when maintenance or testing is being conducted.)	direct observation / shown in Figures in VR-204 Exhibit 2 – System Specifications		
	(2) unit is not on or in the automatic vapor processor mode (except when maintenance or testing is being conducted.) *	diagnostic section within the Veeder-Root ISD Manual (section 12 of IOMM)		
(g) thermal oxidizer	(1) ball valve/s are not in the proper operating configuration as shown in Figures in Exhibit 2 *	direct observation/ shown in VR-204 Exhibit 2 – System Specifications		
(h) clean air separator (CAS)	(1) ball valves are not in the proper operating configuration as shown in Figures in Exhibit 2* (except when maintenance or testing is being conducted.)	direct observation/ shown in VR-204 Exhibit 2 – System Specifications		
<u>, (0, 10)</u>	(2) clean air separator static pressure performance failure *	VR-204 Exhibit 14 - Determination of Static Pressure Performance of the Healy Clean Air Separator		

<sup>\*</sup> When the identified defect is detected in the listed equipment, the defect determination applies to all affected interrelated systems (which may include all systems at the motor vehicle fueling operation).

California Air Resources Board

VR-207 series EMCO Wheaton Retail Phase II EVR System with HIRT VCS 100 Thermal Oxidizer not Including ISD				
equipment defects		verification procedure		
(a) EMCO nozzle	(1) more than 0.4 square inches of a nozzle boot face material is missing (e.g., a triangular or similar shape in which greater than 7/16 inches of the boot face circumference is missing (accumulated))	direct measurement/ observation		
	(2) slit across seven (7) consecutive bellows convolutions	direct measurement/ observation		
(b) all nozzles	(1) insertion interlock mechanism which will allow dispensing when the bellows is uncompressed	direct observation/ GDF-09		
	(2) defective vapor valve	<u>VR-207 Exhibit 7 – Nozzle Bag Test</u> <u>Procedure</u>		
	(3) vapor valve leak rate exceeds 0.07 cubic feet per minute at a pressure of two (2) water column inches	TP-201.2B - Flow and Pressure  Measurement of Vapor Recovery  Equipment		
(c) hoses	(1) 150 ml or more liquid in the vapor path	direct measurement/ sections 6.1 to 6.5 of VR-207 Exhibit 5 - Liquid Removal Test Procedure		
	(2) any hose with a visible opening	direct observation		
(d) thermal oxidizer	(1) ball valves are not in the proper operating configuration as shown in Figures in Exhibit 2 *  (2) thermal oxidizer indicator panel "power on" lamp off *	direct observation/ shown in VR-207 Exhibit 2 – System Specifications direct observation		
(e) vapor return lines	(1) pressure drop through the vapor path exceeds 0.95 water column inches at a flow rate of 60 cubic foot per hour (CFH) and 1.52 water column inches at a flow rate of 80 CFH	TP-201.4 Methodology 1 and Exhibit 6 – Required Items in Conducting TP-201.4		

<sup>\*</sup> When the identified defect is detected in the listed equipment, the defect determination applies to all affected interrelated systems (which may include all systems at the motor vehicle fueling operation).

VR-208 series EMCO Wheaton Retail Phase II EVR System with HIRT VCS 100 Thermal Oxidizer not Including ISD				
<u>equipment</u>	<u>Defects</u>	verification procedure		
(a) EMCO nozzle	(1) more than 0.4 square inches of a nozzle boot face material is missing (e.g., a triangular or similar shape in which greater than 7/16 inches of the boot face circumference is missing (accumulated))	direct measurement/ observation		
	(2) slit across seven (7) consecutive bellows convolutions	direct measurement/ observation		
(b) all nozzles	(1) insertion interlock mechanism which will allow dispensing when the bellows is uncompressed	direct observation/ GDF-09		
	(2) defective vapor valve	<u>VR-208 Exhibit 7 – Nozzle Bag Test</u> <u>Procedure</u>		
	(3) vapor valve leak rate exceeds 0.07 cubic feet per minute at a pressure of two (2) water column inches	TP-201.2B - Flow and Pressure  Measurement of Vapor Recovery  Equipment		
(c) hoses	(1) 150 ml or more liquid in the vapor path	direct measurement/ sections 6.1 to 6.5 of VR-208 Exhibit 5 - Liquid Removal Test Procedure		
	(2) any hose with a visible opening	direct observation		
(d) thermal oxidizer	(1) ball valves are not in the proper operating configuration as shown in Figures in Exhibit 2 *	direct observation/ shown in VR-208 Exhibit 2 – System Specifications		
	(2) thermal oxidizer indicator panel "power on" lamp off *	direct observation		
(e) vapor return lines	(1) pressure drop through the vapor path exceeds 0.95 water column inches at a flow rate of 60 cubic foot per hour (CFH) and 1.52 water column inches at a flow rate of 80 CFH	TP-201.4 Methodology 1 and Exhibit 6 – Required Items in Conducting TP-201.4		

<sup>\*</sup> When the identified defect is detected in the listed equipment, the defect determination applies to all affected interrelated systems (which may include all systems at the motor vehicle fueling operation).

#### Defect Identification Methods Used In the Verification Procedure Column

- -1. TP201.5: Determination (by Volume Meter) of Air to Liquid (A/L) Volume Ratio of Vapor Recovery Systems of Dispensing Facilities, Adopted April 12, 1996
- -2. TP201.4: Determination of Dynamic Pressure Performance of Vapor Recovery Systems of Dispensing Facilities
- -3. TP201.3: Determination of Two-Inch WC Static Pressure Performance of Vapor Recovery Systems of Dispensing Facilities
- 4. GDF-01: Bag Test for Multi-Nozzle Vacuum Assist Systems
- -5. Method 9: 40 Code Federal Regulations Part 60 Appendix A: Reference Method 9/ EPA Section 3.12 Visible Determination of the Opacity of Emissions from Stationary Sources
- -6. G-70--187 Exhibit 5: Fillneck Vapor Pressure Regulation Fueling Test
- 7. EPO No. 26-F-1: Vapor Recovery Systems Field Compliance Testing
- -8. GDF-02: Bag Test for Single-Nozzle Vacuum Assist Systems
- -9. GDF-09: Phase II Balance System Nozzle Insertion Interlock Operation Determination
- 10. G-70-191 Exhibit 2: Specifications for the Healy ORVR Phase II Vapor Recovery System (4.a-4.d)
- 11. G-70-204 Exhibit 2: System Specifications/Vaporsaver (1.A-1.D)
- 12. G-70-209 Exhibit 5: Determination (by Volume Meter) of Air to Liquid Volume Ratio of Vapor Recovery Systems of Dispensing Facilities
- 13. VR-201 Exhibit 4: Determination of Static Pressure Performance of the Healy Clean Air Separator
- 14. VR-201 Exhibit 5: Vapor to Liquid Volume Ratio for Healy Phase II EVR System
- 15. VR-201 Exhibit 7: Nozzle Bag Test Procedure
- 16. VR-202 Exhibit 4: Determination of Static Pressure Performance of the Healy Clean Air Separator
- 17. VR-202 Exhibit 5: Vapor to Liquid Volume Ratio for Healy Phase II EVR System
- 18. VR-202 Exhibit 7: Nozzle Bag Test Procedure
- 19. VR-203 Exhibit 10: Nozzle Bag Test Procedure
- 20. VR-203 Exhibit 5: Liquid Removal Test Procedure
- 21. VR-203 Exhibit9: Determination of VST Processor Activation PressureO

TP-201.2B   Flow and Pressure Measurement of Vapor Recovery Equipment		Defect Ident	ification Methods Specified In the Verification Procedure Column
Suppose   Supp	<u>1.</u>	TP-201.2B	Flow and Pressure Measurement of Vapor Recovery Equipment
TP-201.5   Determination (by Volume Meter) of Air to Liquid (AIL) Volume Ratio of Vapor Recovery. Systems of Dispensing Facilities	<u>2.</u>	<u>TP-201.3</u>	
Recovery Systems of Dispensing Facilities	<u>3.</u>	<u>TP-201.4</u>	Dynamic Back Pressure
5.         GDF-01         Bag Test for Multi-Nozzle Vacuum Assist Systems           6.         GDF-02         Pag Test for Single-Nozzle Insertion Interlock Operation Determination           7.         GDF-09         Phase II Balance System Nozzle Insertion Interlock Operation Determination           8.         Method 9         40 Code Federal Regulations Part 60 Appendix A: Reference Method 9 / EPA Section 3.12 Visible Determination of the Opacity of Emissions from Stationary Sources           9.         EPO No. 26-F-1         Yapor Recovery Systems Field Compliance Testing           10.         G-70-187 Exhibit 5         Fillneck Vapor Pressure Regulation Fueling Test           11.         G-70-191 Exhibit 2         Specifications for the Healy ORVR Phase II Vapor Recovery System (4 a -4 d)           12.         G-70-191 Exhibit 2         Specifications for the Healy ORVR Phase II Vapor Recovery System (4 a -4 d)           13.         G-70-204 Exhibit 2         System Specifications/Vaporsaver (1.A - 1.D)           14.         G-70-209 Exhibit 5         Determination (by Volume Meter) of Air to Liquid Volume Ratio of Vapor Recovery Systems of Dispensing Facilities, Adopted April 12, 1996           15.         VR-201 Exhibit 4         Determination of Static Pressure Performance of the Healy Clean Air Separator           17.         VR-201 Exhibit 4         Determination of Static Pressure Performance of the Healy Clean Air Separator           19.         VR-20	<u>4.</u>	<u>TP-201.5</u>	
6.         GDF-02         Bag Test for Single-Nozzle Vacuum Assist Systems           7.         GDF-09         Phase II Balance System Nozzle Insertion Interlock Operation Determination of Notice of Stations on the Control of Stations Part 60 Appendix A: Reference Method 9/ LPA Section 3.12 Visible Determination of the Opacity of Emissions from Stationary Sources           9.         EPO No. 26-F-1         Vapor Recovery Systems Field Compliance Testing           10.         G-70-191 Exhibit 5         Fillneck Vapor Pressure Regulation Fueling Test           11.         G-70-191 Exhibit 2         Specifications for the Healy ORVR Phase II Vapor Recovery System (4.a-4.d)           12.         G-70-191 IOMM         Healy Systems VP1000 Dispenser Mounted Vacuum Pump Installation & Service Guide, Scheduled Maintenance Instructions, Weekly Inspection, bullet 4 et Seq.           13.         G-70-204 Exhibit 2         System Specifications/Vaporsaver (1.A - 1.D)           14.         G-70-209 Exhibit 5         Determination (by Volume Meter) of Air to Liquid Volume Ratio of Vapor Recovery Systems of Dispensing Facilities, Adopted April 12, 1996           15.         VR-201 IOMM         Healy IOMM, Scheduled Maintenance, section 1.1 paragraph 3 et Seq.           16.         VR-201 Exhibit 4         Determination of Static Pressure Performance of the Healy Clean Air Separator           18.         VR-201 Exhibit 5         Vapor to Liquid Volume Ratio for Healy Phase II EVR System           19.         VR-201 Exhib	<u>5.</u>	GDF-01	Bag Test for Multi-Nozzle Vacuum Assist Systems
8. Method 9 40 Code Federal Regulations Part 60 Appendix A: Reference Method 9 / EPA Section 3.12 Visible Determination of the Opacity of Emissions from Stationary Sources  9. EPO No. 26-F-1 10. G-70-187 Exhibit 5 Fillneck Vapor Pressure Regulation Fueling Test  11. G-70-191 Exhibit 2 Specifications for the Healy ORVR Phase II Vapor Recovery System (4.a-4.d)  12. G-70-191 IOMM Healy Systems VP1000 Dispenser Mounted Vacuum Pump Installation & Service Guide, Scheduled Maintenance Instructions, Weekly Inspection, builet 4 et Seq.  13. G-70-204 Exhibit 2 System Specifications/ Ayorosaver (1 A - 1.D)  14. G-70-204 Exhibit 5 Determination (by Volume Meter) of Air to Liquid Volume Ratio of Vapor Recovery Systems of Dispensing Facilities, Adopted April 12, 1996  15. VR-201 IOMM Healy IOMM, Scheduled Maintenance, section 1.1 paragraph 3 et Seq.  16. VR-201 Exhibit 4 Determination of Static Pressure Performance of the Healy Clean Air Separator  17. VR-201 Exhibit 5 Vapor to Liquid Volume Ratio for Healy Phase II EVR System  19. VR-201 Exhibit 7 Nozzle Bag Test Procedure  20. VR-202 IOMM Healy IOMM, Scheduled Maintenance, section 1.1 paragraph 3 et Seq.  21. VR-202 Exhibit 4 Determination of Static Pressure Performance of the Healy Clean Air Separator  22. VR-202 Exhibit 4 Determination of Static Pressure Performance of the Healy Clean Air Separator  23. VR-202 Exhibit 4 Determination of Static Pressure Performance of the Healy Clean Air Separator  24. VR-202 Exhibit 5 Vapor to Liquid Volume Ratio for Healy Phase II EVR System  25. VR-203 Exhibit 5 Vapor to Liquid Volume Ratio for Healy Phase II EVR System  26. VR-203 Exhibit 5 Vapor to Liquid Volume Ratio for Healy Phase II EVR System  27. VR-203 Exhibit 5 VR-203 Exhibit 5 VR-203 Exhibit 5 VR-203 Exhibit 6 VR-203 Exhibit 7 Nozzle Bag Test Procedure  28. VR-203 Exhibit 7 Nozzle Bag Test Procedure  29. VR-203 Exhibit 1 Determination of Static Pressure Performance of the Healy Clean Air Separator  29. VR-203 Exhibit 1 Determination of Static Pressure Performance of the Heal		<u>GDF-02</u>	Bag Test for Single-Nozzle Vacuum Assist Systems
3.12 Visible Determination of the Opacity of Emissions from Stationary Sources 9. EPO No. 26-F-1 10. G-70-187 Exhibit 5 Fillneck Vapor Pressure Regulation Fueling Test 11. G-70-191 Exhibit 2 Specifications for the Healy ORVR Phase II Vapor Recovery System (4.a-4.d) 12. G-70-191 In March 12 13. G-70-191 In March 12 14. G-70-204 Exhibit 2 System Specifications/Vaporsaver (1.a - 1.D) 15. VR-201 Exhibit 5 Determination (by Volume Meter) of Air to Liquid Volume Ratio of Vapor Recovery Systems of Dispensing Facilities, Adopted April 12, 1996 15. VR-201 Exhibit 5 VR-201 Exhibit 2 System Specifications of Dispensing Facilities, Adopted April 12, 1996 16. VR-201 Exhibit 4 Determination (by Volume Meter) of Air to Liquid Volume Ratio of Vapor Recovery Systems of Dispensing Facilities, Adopted April 12, 1996 16. VR-201 Exhibit 4 Determination of Static Pressure Performance of the Healy Clean Air Separator 17. VR-201 Exhibit 5 VR-201 Exhibit 7 Nozzle Bag Test Procedure 19. VR-202 In March 12 VR-202 Exhibit 7 Nozzle Bag Test Procedure 20. VR-202 Exhibit 4 Determination of Static Pressure Performance of the Healy Clean Air Separator 21. VR-202 Exhibit 5 VR-202 Exhibit 6 VR-202 Exhibit 7 Nozzle Bag Test Procedure 22. VR-202 Exhibit 7 Determination of Static Pressure Performance of the Healy Clean Air Separator 23. VR-202 Exhibit 7 Nozzle Bag Test Procedure 24. VR-202 Exhibit 7 Nozzle Bag Test Procedure 25. VR-203 Exhibit 7 Nozzle Bag Test Procedure 26. VR-203 Exhibit 7 Nozzle Bag Test Procedure 27. VR-203 Exhibit 7 Nozzle Bag Test Procedure 28. VR-203 Exhibit 1 Determination of Static Pressure Performance of the Healy Clean Air Separator 29. VR-203 Exhibit 1 Determination of Static Pressure Performance of the Healy Clean Air Separator 30. VR-203 Exhibit 1 Determination of Static Pressure Performance of the Healy Clean Air Separator 30. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator 30. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separat	<u>7.</u>	<u>GDF-09</u>	Phase II Balance System Nozzle Insertion Interlock Operation Determination
10. G-70-187 Exhibit 5   Fillneck Vapor Pressure Regulation Fueling Test	<u>8.</u>	Method 9	•
11. G-70-191 Exhibit 2   Specifications for the Healy ORVR Phase II Vapor Recovery System (4.a-4.d)     12. G-70-191 IOMM	<u>9.</u>	EPO No. 26-F-1	Vapor Recovery Systems Field Compliance Testing
12. G-70-191 IOMM Healy Systems VP1000 Dispenser Mounted Vacuum Pump Installation & Service Guide, Scheduled Maintenance Instructions. Weekly Inspection, bullet 4 et Seq.  13. G-70-204 Exhibit 2 System Specifications/Vaporsaver (1.A - 1.D)  14. G-70-209 Exhibit 5 Determination (by Volume Meter) of Air to Liquid Volume Ratio of Vapor Recovery Systems of Dispensing Facilities, Adopted April 12, 1996  15. VR-201 IOMM Healy IOMM, Scheduled Maintenance, section 1.1 paragraph 3 et Seq.  16. VR-201 Exhibit 2 System Specifications  17. VR-201 Exhibit 4 Determination of Static Pressure Performance of the Healy Clean Air Separator  18. VR-201 Exhibit 5 Vapor to Liquid Volume Ratio for Healy Phase II EVR System  19. VR-201 Exhibit 7 Nozzle Bag Test Procedure  20. VR-202 Exhibit 2 System Specifications  21. VR-202 Exhibit 4 Determination of Static Pressure Performance of the Healy Clean Air Separator  22. VR-202 Exhibit 4 Determination of Static Pressure Performance of the Healy Clean Air Separator  23. VR-202 Exhibit 5 Vapor to Liquid Volume Ratio for Healy Phase II EVR System  24. VR-202 Exhibit 6 Vapor to Liquid Volume Ratio for Healy Phase II EVR System  25. VR-203 Exhibit 7 Nozzle Bag Test Procedure  26. VR-203 Exhibit 7 Nozzle Bag Test Procedure  27. VR-203 Exhibit 7 Nozzle Bag Test Procedure  28. VR-203 Exhibit 7 Nozzle Bag Test Procedure  29. VR-203 Exhibit 13 Hirt VCS 100 Processor with Indicator Panel Operability Test Procedure  29. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  29. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  29. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  29. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  29. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  29. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air	<u>10.</u>	G-70-187 Exhibit 5	Fillneck Vapor Pressure Regulation Fueling Test
Guide, Scheduled Maintenance Instructions, Weekly Inspection, bullet 4 et Seq.  13. G-70-204 Exhibit 2 System Specifications/Vaporsaver (1.A - 1.D)  14. G-70-209 Exhibit 5 Determination (by Volume Meter) of Air to Liquid Volume Ratio of Vapor Recovery Systems of Dispensing Facilities, Adopted April 12, 1996  15. VR-201 IOMM Healy IOMM, Scheduled Maintenance, section 1.1 paragraph 3 et Seq.  16. VR-201 Exhibit 2 System Specifications  17. VR-201 Exhibit 4 Determination of Static Pressure Performance of the Healy Clean Air Separator  18. VR-201 Exhibit 5 Vapor to Liquid Volume Ratio for Healy Phase II EVR System  19. VR-201 Exhibit 7 Nozzle Bag Test Procedure  20. VR-202 IOMM Healy IOMM, Scheduled Maintenance, section 1.1 paragraph 3 et Seq.  21. VR-202 Exhibit 2 System Specifications  22. VR-202 Exhibit 2 System Specifications  23. VR-202 Exhibit 4 Determination of Static Pressure Performance of the Healy Clean Air Separator  23. VR-202 Exhibit 5 Vapor to Liquid Volume Ratio for Healy Phase II EVR System  24. VR-202 Exhibit 5 Vapor to Liquid Volume Ratio for Healy Phase II EVR System  25. VR-203 Exhibit 7 Nozzle Bag Test Procedure  26. VR-203 Exhibit 5 Liquid Removal Test Procedure (sections 6.1 to 6.5)  27. VR-203 Exhibit 7 Nozzle Bag Test Procedure  28. VR-203 Exhibit 1 Determination of Static Pressure Performance of the Healy Clean Air Separator  29. VR-203 Exhibit 1 Determination of Static Pressure Performance of the Healy Clean Air Separator  29. VR-203 Exhibit 1 Determination of Static Pressure Performance of the Healy Clean Air Separator  29. VR-203 Exhibit 1 Determination of Static Pressure Performance of the Healy Clean Air Separator  29. VR-203 Exhibit 10 Determination of Static Pressure Performance of the Healy Clean Air Separator  29. VR-203 Exhibit 10 Determination of Static Pressure Performance of the Healy Clean Air Separator  29. VR-203 Exhibit 10 Determination of Static Pressure Performance of the Healy Clean Air Separator  20. VR-203 Exhibit 10 Determination of Static Pressure Performance of th	<u>11.</u>	G-70-191 Exhibit 2	Specifications for the Healy ORVR Phase II Vapor Recovery System (4.a-4.d)
14. G-70-209 Exhibit 5 Determination (by Volume Meter) of Air to Liquid Volume Ratio of Vapor Recovery Systems of Dispensing Facilities, Adopted April 12, 1996  15. VR-201 IOMM Healy IOMM, Scheduled Maintenance, section 1.1 paragraph 3 et Seq.  16. VR-201 Exhibit 2 System Specifications  17. VR-201 Exhibit 4 Determination of Static Pressure Performance of the Healy Clean Air Separator  18. VR-201 Exhibit 5 Vapor to Liquid Volume Ratio for Healy Phase II EVR System  19. VR-201 Exhibit 7 Nozzle Bag Test Procedure  20. VR-202 IOMM Healy IOMM, Scheduled Maintenance, section 1.1 paragraph 3 et Seq.  21. VR-202 Exhibit 2 System Specifications  22. VR-202 Exhibit 4 Determination of Static Pressure Performance of the Healy Clean Air Separator  23. VR-202 Exhibit 5 Vapor to Liquid Volume Ratio for Healy Phase II EVR System  24. VR-202 Exhibit 7 Nozzle Bag Test Procedure  25. VR-203 Exhibit 5 Liquid Removal Test Procedure (sections 6.1 to 6.5)  27. VR-203 Exhibit 13 Hirt VCS 100 Processor with Indicator Panel Operability Test Procedure  29. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  29. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  29. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  29. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  29. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  29. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  29. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  29. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  29. VR-203 Exhibit 14 Determination of Static Pressure Management Control (section 15 of IOMM)  30. VR-204 Exhibit 2 System Specifications  31. VR-204 Exhibit 2 System Specifications	<u>12.</u>	G-70-191 IOMM	
Vapor Recovery Systems of Dispensing Facilities, Adopted April 12, 1996	<u>13.</u>	G-70-204 Exhibit 2	System Specifications/Vaporsaver (1.A - 1.D)
16. VR-201 Exhibit 2 System Specifications  17. VR-201 Exhibit 4 Determination of Static Pressure Performance of the Healy Clean Air Separator  18. VR-201 Exhibit 5 Vapor to Liquid Volume Ratio for Healy Phase II EVR System  19. VR-201 Exhibit 7 Nozzle Bag Test Procedure  20. VR-202 IOMM Healy IOMM, Scheduled Maintenance, section 1.1 paragraph 3 et Seq.  21. VR-202 Exhibit 2 System Specifications  22. VR-202 Exhibit 4 Determination of Static Pressure Performance of the Healy Clean Air Separator  23. VR-202 Exhibit 5 Vapor to Liquid Volume Ratio for Healy Phase II EVR System  24. VR-202 Exhibit 7 Nozzle Bag Test Procedure  25. VR-203 Exhibit 2 System Specifications  26. VR-203 Exhibit 5 Liquid Removal Test Procedure (sections 6.1 to 6.5)  27. VR-203 Exhibit 7 Nozzle Bag Test Procedure  28. VR-203 Exhibit 13 Hirt VCS 100 Processor with Indicator Panel Operability Test Procedure  29. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  30. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  30. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  30. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  30. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  30. VR-203 Exhibit 14 Determination of Static Pressure Management Control (section 12 of IOMM)  31. VR-203 Section 15 of IOMM  32. VR-204 Exhibit 2 System Specifications  33. VR-204 Exhibit 5 Liquid Removal Test Procedure (sections 6.1 to 6.5)	<u>14.</u>	G-70-209 Exhibit 5	
17. VR-201 Exhibit 4 Determination of Static Pressure Performance of the Healy Clean Air Separator  18. VR-201 Exhibit 5 Vapor to Liquid Volume Ratio for Healy Phase II EVR System  19. VR-201 Exhibit 7 Nozzle Bag Test Procedure  20. VR-202 IOMM Healy IOMM, Scheduled Maintenance, section 1.1 paragraph 3 et Seq.  21. VR-202 Exhibit 2 System Specifications  22. VR-202 Exhibit 4 Determination of Static Pressure Performance of the Healy Clean Air Separator  23. VR-202 Exhibit 5 Vapor to Liquid Volume Ratio for Healy Phase II EVR System  24. VR-202 Exhibit 7 Nozzle Bag Test Procedure  25. VR-203 Exhibit 2 System Specifications  26. VR-203 Exhibit 5 Liquid Removal Test Procedure (sections 6.1 to 6.5)  27. VR-203 Exhibit 7 Nozzle Bag Test Procedure  28. VR-203 Exhibit 13 Hirt VCS 100 Processor with Indicator Panel Operability Test Procedure  29. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  30. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  30. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  30. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  30. VR-203 Exhibit 14 Determination of Static Pressure Management Control (section 12 of IOMM)  31. VR-203 section 15 of IOMM  32. VR-204 Exhibit 2 System Specifications  33. VR-204 Exhibit 5 Liquid Removal Test Procedure (sections 6.1 to 6.5)	<u>15.</u>	VR-201 IOMM	Healy IOMM, Scheduled Maintenance, section 1.1 paragraph 3 et Seq.
18. VR-201 Exhibit 5	<u>16.</u>	VR-201 Exhibit 2	System Specifications
19. VR-201 Exhibit 7  20. VR-202 IOMM  Healy IOMM, Scheduled Maintenance, section 1.1 paragraph 3 et Seq.  21. VR-202 Exhibit 2  22. VR-202 Exhibit 4  Determination of Static Pressure Performance of the Healy Clean Air Separator  23. VR-202 Exhibit 5  Vapor to Liquid Volume Ratio for Healy Phase II EVR System  24. VR-202 Exhibit 7  Nozzle Bag Test Procedure  25. VR-203 Exhibit 2  System Specifications  26. VR-203 Exhibit 5  Liquid Removal Test Procedure (sections 6.1 to 6.5)  27. VR-203 Exhibit 7  Nozzle Bag Test Procedure  28. VR-203 Exhibit 13  Hirt VCS 100 Processor with Indicator Panel Operability Test Procedure  29. VR-203 Exhibit 14  Determination of Static Pressure Performance of the Healy Clean Air Separator  VR-203 Exhibit 14  Determination of Static Pressure Performance of the Healy Clean Air Separator  VR-203 Sextino 12 of Diagnostic section within the VST ECS Membrane Processor: Veeder-Root Pressure Management Control (section 12 of IOMM)  31. VR-203 section 15 of IOMM  VR-203 Sextion 15 of IOMM  VR-204 Exhibit 2  System Specifications  32. VR-204 Exhibit 5  Liquid Removal Test Procedure (sections 6.1 to 6.5)	<u>17.</u>	VR-201 Exhibit 4	Determination of Static Pressure Performance of the Healy Clean Air Separator
20.VR-202 IOMMHealy IOMM, Scheduled Maintenance, section 1.1 paragraph 3 et Seq.21.VR-202 Exhibit 2System Specifications22.VR-202 Exhibit 4Determination of Static Pressure Performance of the Healy Clean Air Separator23.VR-202 Exhibit 5Vapor to Liquid Volume Ratio for Healy Phase II EVR System24.VR-202 Exhibit 7Nozzle Bag Test Procedure25.VR-203 Exhibit 2System Specifications26.VR-203 Exhibit 5Liquid Removal Test Procedure (sections 6.1 to 6.5)27.VR-203 Exhibit 7Nozzle Bag Test Procedure28.VR-203 Exhibit 13Hirt VCS 100 Processor with Indicator Panel Operability Test Procedure29.VR-203 Exhibit 14Determination of Static Pressure Performance of the Healy Clean Air Separator30.VR-203 section 12 of IOMMDiagnostic section within the VST ECS Membrane Processor: Veeder-Root Pressure Management Control (section 12 of IOMM)31.VR-203 section 15 of IOMMPMC Diagnostic report per 'PMC Diagnostic Menus' section within the Veeder-Root Vapor Polisher: Pressure Management Control (section 15 of IOMM)32.VR-204 Exhibit 2System Specifications33.VR-204 Exhibit 5Liquid Removal Test Procedure (sections 6.1 to 6.5)	<u>18.</u>	VR-201 Exhibit 5	Vapor to Liquid Volume Ratio for Healy Phase II EVR System
21.VR-202 Exhibit 2System Specifications22.VR-202 Exhibit 4Determination of Static Pressure Performance of the Healy Clean Air Separator23.VR-202 Exhibit 5Vapor to Liquid Volume Ratio for Healy Phase II EVR System24.VR-202 Exhibit 7Nozzle Bag Test Procedure25.VR-203 Exhibit 2System Specifications26.VR-203 Exhibit 5Liquid Removal Test Procedure (sections 6.1 to 6.5)27.VR-203 Exhibit 7Nozzle Bag Test Procedure28.VR-203 Exhibit 13Hirt VCS 100 Processor with Indicator Panel Operability Test Procedure29.VR-203 Exhibit 14Determination of Static Pressure Performance of the Healy Clean Air Separator30.VR-203 section 12 of IOMMDiagnostic section within the VST ECS Membrane Processor: Veeder-Root Pressure Management Control (section 12 of IOMM)31.VR-203 section 15 of IOMMPMC Diagnostic report per 'PMC Diagnostic Menus' section within the Veeder-Root Vapor Polisher: Pressure Management Control (section 15 of IOMM)32.VR-204 Exhibit 2System Specifications33.VR-204 Exhibit 5Liquid Removal Test Procedure (sections 6.1 to 6.5)	<u>19.</u>	VR-201 Exhibit 7	Nozzle Bag Test Procedure
22.VR-202 Exhibit 4Determination of Static Pressure Performance of the Healy Clean Air Separator23.VR-202 Exhibit 5Vapor to Liquid Volume Ratio for Healy Phase II EVR System24.VR-202 Exhibit 7Nozzle Bag Test Procedure25.VR-203 Exhibit 2System Specifications26.VR-203 Exhibit 5Liquid Removal Test Procedure (sections 6.1 to 6.5)27.VR-203 Exhibit 7Nozzle Bag Test Procedure28.VR-203 Exhibit 13Hirt VCS 100 Processor with Indicator Panel Operability Test Procedure29.VR-203 Exhibit 14Determination of Static Pressure Performance of the Healy Clean Air Separator30.VR-203: section 12 of IOMMDiagnostic section within the VST ECS Membrane Processor: Veeder-Root Pressure Management Control (section 12 of IOMM)31.VR-203: section 15 of IOMMPMC Diagnostic report per 'PMC Diagnostic Menus' section within the Veeder-Root Vapor Polisher: Pressure Management Control (section 15 of IOMM)32.VR-204 Exhibit 2System Specifications33.VR-204 Exhibit 5Liquid Removal Test Procedure (sections 6.1 to 6.5)	<u>20.</u>	VR-202 IOMM	Healy IOMM, Scheduled Maintenance, section 1.1 paragraph 3 et Seq.
23. VR-202 Exhibit 5	<u>21.</u>	VR-202 Exhibit 2	System Specifications
24.VR-202 Exhibit 7Nozzle Bag Test Procedure25.VR-203 Exhibit 2System Specifications26.VR-203 Exhibit 5Liquid Removal Test Procedure (sections 6.1 to 6.5)27.VR-203 Exhibit 7Nozzle Bag Test Procedure28.VR-203 Exhibit 13Hirt VCS 100 Processor with Indicator Panel Operability Test Procedure29.VR-203 Exhibit 14Determination of Static Pressure Performance of the Healy Clean Air Separator30.VR-203: section 12 of IOMMDiagnostic section within the VST ECS Membrane Processor: Veeder-Root Pressure Management Control (section 12 of IOMM)31.VR-203: section 15 of IOMMPMC Diagnostic report per 'PMC Diagnostic Menus' section within the Veeder-Root Vapor Polisher: Pressure Management Control (section 15 of IOMM)32.VR-204 Exhibit 2System Specifications33.VR-204 Exhibit 5Liquid Removal Test Procedure (sections 6.1 to 6.5)	<u>22.</u>	VR-202 Exhibit 4	Determination of Static Pressure Performance of the Healy Clean Air Separator
25. VR-203 Exhibit 2  26. VR-203 Exhibit 5  Liquid Removal Test Procedure (sections 6.1 to 6.5)  27. VR-203 Exhibit 7  Nozzle Bag Test Procedure  28. VR-203 Exhibit 13  Hirt VCS 100 Processor with Indicator Panel Operability Test Procedure  29. VR-203 Exhibit 14  Determination of Static Pressure Performance of the Healy Clean Air Separator  30. VR-203: section 12 of IOMM  VR-203: section 15 of IOMM  VR-203: section 15 of IOMM  VR-204 Exhibit 2  System Specifications  32. VR-204 Exhibit 5  Liquid Removal Test Procedure (sections 6.1 to 6.5)	<u>23.</u>	VR-202 Exhibit 5	Vapor to Liquid Volume Ratio for Healy Phase II EVR System
26. VR-203 Exhibit 5 Liquid Removal Test Procedure (sections 6.1 to 6.5)  27. VR-203 Exhibit 7 Nozzle Bag Test Procedure  28. VR-203 Exhibit 13 Hirt VCS 100 Processor with Indicator Panel Operability Test Procedure  29. VR-203 Exhibit 14 Determination of Static Pressure Performance of the Healy Clean Air Separator  30. VR-203: section 12 of IOMM Diagnostic section within the VST ECS Membrane Processor: Veeder-Root Pressure Management Control (section 12 of IOMM)  31. VR-203: section 15 of IOMM VR-203: section 15 of IOMM Veeder-Root Vapor Polisher: Pressure Management Control (section 15 of IOMM)  32. VR-204 Exhibit 2 System Specifications  Liquid Removal Test Procedure (sections 6.1 to 6.5)	<u>24.</u>	VR-202 Exhibit 7	Nozzle Bag Test Procedure
27.VR-203 Exhibit 7Nozzle Bag Test Procedure28.VR-203 Exhibit 13Hirt VCS 100 Processor with Indicator Panel Operability Test Procedure29.VR-203 Exhibit 14Determination of Static Pressure Performance of the Healy Clean Air Separator30.VR-203: section 12 of IOMMDiagnostic section within the VST ECS Membrane Processor: Veeder-Root Pressure Management Control (section 12 of IOMM)31.VR-203: section 15 of IOMMPMC Diagnostic report per 'PMC Diagnostic Menus' section within the Veeder-Root Vapor Polisher: Pressure Management Control (section 15 of IOMM)32.VR-204 Exhibit 2System Specifications33.VR-204 Exhibit 5Liquid Removal Test Procedure (sections 6.1 to 6.5)	<u>25.</u>	VR-203 Exhibit 2	System Specifications
28.VR-203 Exhibit 13Hirt VCS 100 Processor with Indicator Panel Operability Test Procedure29.VR-203 Exhibit 14Determination of Static Pressure Performance of the Healy Clean Air Separator30.VR-203: section 12 of IOMMDiagnostic section within the VST ECS Membrane Processor: Veeder-Root Pressure Management Control (section 12 of IOMM)31.VR-203: section 15 of IOMMPMC Diagnostic report per 'PMC Diagnostic Menus' section within the Veeder-Root Vapor Polisher: Pressure Management Control (section 15 of IOMM)32.VR-204 Exhibit 2System Specifications33.VR-204 Exhibit 5Liquid Removal Test Procedure (sections 6.1 to 6.5)	<u>26.</u>	VR-203 Exhibit 5	Liquid Removal Test Procedure (sections 6.1 to 6.5)
29.VR-203 Exhibit 14Determination of Static Pressure Performance of the Healy Clean Air Separator30.VR-203: section 12 of IOMMDiagnostic section within the VST ECS Membrane Processor: Veeder-Root Pressure Management Control (section 12 of IOMM)31.VR-203: section 15 of IOMMPMC Diagnostic report per 'PMC Diagnostic Menus' section within the Veeder-Root Vapor Polisher: Pressure Management Control (section 15 of IOMM)32.VR-204 Exhibit 2System Specifications33.VR-204 Exhibit 5Liquid Removal Test Procedure (sections 6.1 to 6.5)	<u>27.</u>	VR-203 Exhibit 7	Nozzle Bag Test Procedure
30.     VR-203: section 12 of IOMM     Diagnostic section within the VST ECS Membrane Processor: Veeder-Root Pressure Management Control (section 12 of IOMM)       31.     VR-203: section 15 of IOMM     PMC Diagnostic report per 'PMC Diagnostic Menus' section within the Veeder-Root Vapor Polisher: Pressure Management Control (section 15 of IOMM)       32.     VR-204 Exhibit 2     System Specifications       33.     VR-204 Exhibit 5     Liquid Removal Test Procedure (sections 6.1 to 6.5)	<u>28.</u>	VR-203 Exhibit 13	Hirt VCS 100 Processor with Indicator Panel Operability Test Procedure
IOMM   Veeder-Root Pressure Management Control (section 12 of IOMM)	<u>29.</u>	VR-203 Exhibit 14	Determination of Static Pressure Performance of the Healy Clean Air Separator
IOMM     Veeder-Root Vapor Polisher: Pressure Management Control (section 15 of IOMM)       32.     VR-204 Exhibit 2     System Specifications       33.     VR-204 Exhibit 5     Liquid Removal Test Procedure (sections 6.1 to 6.5)	<u>30.</u>		
33. VR-204 Exhibit 5 Liquid Removal Test Procedure (sections 6.1 to 6.5)	<u>31.</u>		
	<u>32.</u>	VR-204 Exhibit 2	System Specifications
34. VR-204 Exhibit 7 Nozzle Bag Test Procedure	<u>33.</u>	VR-204 Exhibit 5	Liquid Removal Test Procedure (sections 6.1 to 6.5)
	<u>34.</u>	VR-204 Exhibit 7	Nozzle Bag Test Procedure

	Defect Identification Methods Specified In the Verification Procedure Column				
<u>35.</u>	<u>VR-204 Exhibit 13</u>	Hirt VCS 100 Processor with Indicator Panel Operability Test Procedure			
<u>36.</u>	<u>VR-204 Exhibit 14</u>	Determination of Static Pressure Performance of the Healy Clean Air Separator			
<u>37.</u>	VR-204: section 12 of IOMM	'Diagnostic' section within the Veeder-Root ISD Manual (section 12 of IOMM)			
<u>38.</u>	VR-207 Exhibit 2	System Specifications			
<u>39.</u>	VR-207 Exhibit 5	Liquid Removal Test Procedure (sections 6.1 to 6.5)			
<u>40.</u>	VR-207 Exhibit 6	Required Items in Conducting TP-201.4			
<u>41.</u>	VR-207 Exhibit 7	Nozzle Bag Test Procedure			
<u>42.</u>	VR-208 Exhibit 2	System Specifications			
<u>43.</u>	VR-208 Exhibit 5	Liquid Removal Test Procedure (sections 6.1 to 6.5)			
<u>44.</u>	VR-208 Exhibit 6	Required Items in Conducting TP-201.4			
<u>45.</u>	VR-208 Exhibit 7	Nozzle Bag Test Procedure			
<u>46.</u>	VR-208 Exhibit 8	Indicator Panel Operability Test Procedure			