

Alternative Maritime Power at the Port of Los Angeles







Berth 100



Port of Los Angeles Berth 100



LA D P

- 34.5 KV in Trench, Street to Substation
- POLA 6.6 KV Substation on Terminal







AMP Design& Construction

- LADWP Design & Construction
 Utility Transformer Station
- POLA Design & Construction Backland, Trenching, Wharf & Cable Management system







AMP Design & Construction

- New Facility
- Retrofitting an in-use Terminal
 - Phased Construction
 - Contractor Accessibility
 - Terminal Security & Safety Plans
 - Storage of Materials







AMP - Backland



Utility Transformer 34.5/6.6 kV, 7.5 MVA



Main & Metering Equipment (6.6 kV)







AMP Trenching & Switchgear










AMP Wharf Receptacle Box









AMP Under Wharf Conduit













AMP Wharf Receptacle Box










AMP Box Construction













AMP Power Outlet Vault













AMP System Schedule









AMP: The Future

PIER 400 (Phase II)

- AMP Power Vault constructed
- Conduit installed

Berth 215 - 221


- Commenced AMP design
- M/V NYK Atlas AMP outfitted (arrived POLA on August 2004)







AMP Cruise Terminal





AMP Infrastructure Cost



Backland

Equipment

• Berth 100:

\$6,800,000

\$1,000,000

Berth 212-215: \$2,500,000

• Pier 400:

\$1,270,000







Thank You.

